

# Precise Aerial Measurement Report

AGR Roofing and Construction



8808 South 69th Circle, Papillion, NE 68157




AGR Roofing and Construction  
340 N 76th St  
Omaha, NE 68114

tel. 402-639-1218  
email: [info@agr-mw.com](mailto:info@agr-mw.com)  
[www.agrroofingandconstruction.com](http://www.agrroofingandconstruction.com)

8808 South 69th Circle, Papillion, NE 68157

Report: 60585885



In this 3D model, facets appear as semi-transparent to reveal overhangs.

### Claim Information

ClaimNumber: 240613539

## PREPARED FOR

Contact:	Brandon Williams
Company:	AGR Roofing and Construction
Address:	340 N 76th St Omaha, NE 68114
Phone:	402-639-1218

## TABLE OF CONTENTS

Images .....	1
Length Diagram .....	4
Pitch Diagram .....	5
Area Diagram .....	6
Notes Diagram.....	7
Report Summary.....	8

## MEASUREMENTS

Total Roof Area =1,776 sq ft  
 Total Roof Facets =9  
 Predominant Pitch =5/12  
 Number of Stories >1  
 Total Ridges/Hips =59 ft  
 Total Valleys =41 ft  
 Total Rakes =131 ft  
 Total Eaves =125 ft

Measurements provided by [www.eagleview.com](http://www.eagleview.com)


Certified Accurate

[www.eagleview.com/Guarantee.aspx](http://www.eagleview.com/Guarantee.aspx)

## IMAGES

The following aerial images show different angles of this structure for your reference.

Top View




## IMAGES

North Side



South Side






## IMAGES

East Side




West Side



# LENGTH DIAGRAM

Total Line Lengths:


**Ridges = 59 ft**
**Hips = 0 ft**
**Valleys = 41 ft**
**Rakes = 131 ft**
**Eaves = 125 ft**
**Flashing = 60 ft**
**Step flashing = 16 ft**
**Parapets = 0 ft**


**Note:** This diagram contains segment lengths (rounded to the nearest whole number) over 5.0 Feet. In some cases, segment labels have been removed for readability. Plus signs preface some numbers to avoid confusion when rotated (e.g. +6 and +9).



## AREA DIAGRAM

Total Area = 1,776 sq ft, with 9 facets.




Note: This diagram shows the square feet of each roof facet (rounded to the nearest Foot). The total area in square feet, at the top of this page, is based on the non-rounded values of each roof facet (rounded to the nearest square foot after being totaled).



## NOTES DIAGRAM

Roof facets are labeled from smallest to largest (A to Z) for easy reference.



Note: This diagram also appears in the Property Owner Report.

## REPORT SUMMARY

### All Structures

#### Areas per Pitch

Roof Pitches	4/12	5/12	6/12
Area (sq ft)	336.1	1174.3	265.6
% of Roof	18.9%	66.1%	15%

The table above lists each pitch on this roof and the total area and percent (both rounded) of the roof with that pitch.

#### Structure Complexity

Simple	Normal	Complex
--------	--------	---------

#### Waste Calculation


NOTE: This waste calculation table is for asphalt shingle roofing applications. All values in table below only include roof areas of 3/12 pitch or greater. For total measurements of all pitches, please refer to the **Lengths, Areas, and Pitches** section below.

Waste %	0%	1%	6%	9%	11%	13%	16%	21%	26%
Area (Sq ft)	1776	1794	1883	1936	1972	2007	2061	2149	2238
Squares *	18.00	18.00	19.00	19.66	20.00	20.33	20.66	21.66	22.66
	Measured				Suggested				

\* Squares are rounded up to the 1/3 of a square

Additional materials needed for ridge, hip, and starter lengths are not included in the above table. The provided suggested waste factor is intended to serve as a guide—actual waste percentages may differ based upon several variables that EagleView does not control. These waste factor variables include, but are not limited to, individual installation techniques, crew experiences, asphalt shingle material subtleties, and potential salvage from the site. Individual results may vary from the suggested waste factor that EagleView has provided. The suggested waste is not to replace or substitute for experience or judgment as to any given replacement or repair work.

### All Structures Totals



Total Roof Facets = 9

#### Lengths, Areas and Pitches

Ridges = 59 ft (4 Ridges)  
Hips = 0 ft (0 Hips).  
Valleys = 41 ft (2 Valleys)  
Rakes† = 131 ft (14 Rakes)  
Eaves/Starter‡ = 125 ft (8 Eaves)  
Drip Edge (Eaves + Rakes) = 256 ft (22 Lengths)  
Parapet Walls = 0 (0 Lengths).  
Flashing = 60 ft (4 Lengths)  
Step flashing = 16 ft (4 Lengths)  
Predominant Pitch = 5/12  
**Total Area (All Pitches) = 1,776 sq ft**

#### Property Location

Longitude = -96.0183180  
Latitude = 41.1706032

#### Notes

This was ordered as a residential property. There were no changes to the structure in the past four years.

† Rakes are defined as roof edges that are sloped (not level).

‡ Eaves are defined as roof edges that are not sloped and level.

8808 South 69th Circle, Papillion, NE 68157

Report: 60585885

**Online Maps**

Online map of property

[http://maps.google.com/maps?f=g&source=s\\_q&hl=en&geocode=&q=8808+South+69th+Circle,Papillion,NE,68157](http://maps.google.com/maps?f=g&source=s_q&hl=en&geocode=&q=8808+South+69th+Circle,Papillion,NE,68157)

Directions from AGR Roofing and Construction to this property

[http://maps.google.com/maps?f=d&source=s\\_d&saddr=340+N+76th+St,Omaha,NE,68114&daddr=8808+South+69th+Circle,Papillion,NE,68157](http://maps.google.com/maps?f=d&source=s_d&saddr=340+N+76th+St,Omaha,NE,68114&daddr=8808+South+69th+Circle,Papillion,NE,68157)

8808 South 69th Circle, Papillion, NE 68157

Report: 60585885

**IMPORTANT LEGAL NOTICE AND DISCLAIMER****Notice and Disclaimer**

No Warranty: The Copyrighted Materials are provided to you "as is," and you agree to use it at your own risk.

EagleView Technologies makes no guarantees, representations or warranties of any kind, express or implied, arising by law or otherwise, including but not limited to, content, quality, accuracy, completeness, effectiveness, reliability, fitness for a particular purpose, usefulness, use or results to be obtained from the Copyrighted Materials.

Contractors agree to always conduct a preliminary site survey to verify Roof Report ordered. In the event of an error in a Report, your sole remedy will be a refund of the fees paid by you to obtain this Report.